


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Rice County. Sec. 11 Twp. 20S Rge. 9 (X) (W)
Location as "NE/CNW/SW" or footage from lines NW NW SE
Lease Owner D & D Drilling Co., Inc.
Lease Name Sharpe Well No. 1
Office Address 308 Schweiter Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed June 27, 19 64
Application for plugging filed June 29, 19 64
Application for plugging approved _____ 19 _____
Plugging commenced June 27, 19 64
Plugging completed June 27, 19 64
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bert Stafford
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3378 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface pipe		0	227'	8-5/8"	6-19-64	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fill hole with heavy mud to 225' from surface. Set plug with 25 sacks cement. Fill surface casing with heavy mud to 20'. Set plug with 10 sacks cement. 2 sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

JUN 30 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Dunne-Gardner Drilling Co., Inc.
Address 300 Schweiter Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Don Gardner (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
300 Schweiter Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of June, 19 64

My commission expires November 9, 1965

[Signature]
Marilyn E. Fox
Notary Public.

DRILLER'S LOG

OPERATOR: D & D Drilling Co., Inc.
308 Schweiter Building, Wichita, Kansas

CONTRACTOR: Dunne-Gardner Drilling Co., Inc.
300 Schweiter Building, Wichita, Kansas

LEASE: Sharpe

WELL: No. 1

LOCATION: NW NW SE Section 11-20S-9W
Rice County, Kansas

DATE COMMENCED: June 19, 1964

DATE COMPLETED: June 27, 1964

TOTAL DEPTH: 3378'

CASING: Set 8-5/8" surface pipe at 227' with 175 sacks cement.

<u>FROM:</u>	<u>TO</u>	
0	40	Surface Clay
40	170	Sand
170	227	Red Bed
227	242	Shale
242	260	Anhydrite
260	775	Red Bed
775	1150	Shale
1150	1185	Shale and Lime
1185	1590	Lime
1590	1900	Lime and Shale
1900	2130	Shale and Lime Streaks
2130	2558	Shale and Lime
2558	2705	Lime
2705	2840	Shale and Lime
2840	3295	Lime
3295	3341	Shale and Sand
3341	3378	Lime
3378		Total Depth

RECEIVED
STATE CORPORATION COMMISSION

JUN 30 1964


CONSERVATION DIVISION
Wichita, Kansas

I certify the above to be true and correct to the best of my knowledge and belief.

DUNNE-GARDNER DRILLING CO., INC.

By 
Don Gardner

Subscribed and sworn to before me this 29th day of June, 1964.


Marilyn E. Fox, Notary Public

My Commission Expires:
November 9, 1965