

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-145-21,410.0000

LEASE NAME OETKEN

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1-2

330 FT. from (S) Section Line

2310 FT. from (E) Section Line

SEC. 2 TWP. 20 RGE. 16 (X) or (W)

LEASE OPERATOR CHIEF DRILLING, INC.

COUNTY Pawnee

ADDRESS 120 S. Market #300 Wichita, KS. 67202

Date Well Completed 12-1-92

PHONE# (316) 262-3791 OPERATORS LICENSE NO. 5886

Plugging Commenced 12-1-92

Character of Well D&A

Plugging Completed 12-1-92

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on November 30, 1992 (date)

by Duane Rankin (KCC District Agent's Name)

Is ACO-1 filed? by operator if not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3825'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface		0	1016'	8 5/8"	1016'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

155 SX. 60/40 Pozmix, 6% Gel Plugged @ 3650' W/40 sx., 1040' W/50 sx., 500' W/40 sx., 15' sx. in rathole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor L. D. Drilling, Inc. License No. 6039

Address R.R. 1 Box 183 B Great Bend, KS. 67530


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Chief Drilling, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

L. D. Davis (Employee of Operator) or (XXXXXXXX) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) L. D. Davis RECEIVED
L. D. Davis CORPORATION COMMISSION

(Address) R.R. 1 Box 183 B, Great Bend, KS 67530
DEC 7 1992



SUBSCRIBED AND SWORN TO before me this 4th day of December, 1992

Bessie M. DeWerff
Notary Public
Bessie M. DeWerff

My Commission Expires: 5-20-93

DRILLERS WELL LOG

0 - 200 Surface Soil & shale
 200 - 780 Shale, sand & red beds
 780 -1015 Shale
 1015 -1038 Anhy
 1038 -1440 Shale
 1440 -3430 Lime & Shale
 3430 -3689 Lime
 3689 -3825 Arb.
 3825 RTD

Chief Drilling, Inc.
 Oetken # 1-2
 SW SW SE Sec. 2-20S-16W
 Pawnee County, Kansas

ELEVATION: 1988 GR

SURFACE CASING:

8 5/8" set @ 1016' W/375 sx.
 60/40 Pozmix, 2% Gel, 3%cc

A F F I D A V I T


STATE OF KANSAS)
 COUNTY OF BARTON)^{ss}

L. D. DAVIS of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

L. D. Davis

 L. D. Davis

Subscribed and sworn to before me this 4th day of December, 1992:



Bessie M. DeWerff

 Bessie M. DeWerff

My Commission expires: 5-20-93

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 7 1992
 DIVISION
 State, Kansas