

15.145.00990.0000


OR

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biltmore Building
Wichita, Kansas

NORTH



Locate well correctly on above Section Flat

Pawnee County. Sec. 2 Twp. 20 Rge. (E) 16 (W)
Location as "NE¼NW¼SW¼" or footage from lines SE SE SE
Lease Owner Sterling Drilling Company
Lease Name Bowyer Well No. 1
Office Address Sterling, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 18th, 1946
Application for plugging filed October 18th, 1946
Application for plugging approved October 18th, 1946
Plugging commenced October 19th, 1946
Plugging completed October 19th, 1946
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3810 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled Out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 1025' | none |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy mud to 300 feet from top and cemented with twenty sacks cement. Filled to thirty feet from top and ran 10 sacks cement.

pd
10/30/46
ka

PLUGGING
2 20 1600
78 LINE 32



(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Sterling Drilling Company
Address Sterling, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.
Rollin Mead, (operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Rollin Mead*
Sterling, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 22nd day of October, 1946

My commission expires Sept. 17th, 1949. *J. A. Tuller* Notary Public.

STERLING DRILLING COMPANY
STERLING, KANSAS

15.145.00990.0000

WELL LOG ----- BOWYER #1

Location -- SE SE SE Section 2-20-16W, Pawnee County, Kansas

Elevation -- 1999

Date Commenced -- Sept. 28th, 1946

Date Completed -- Oct. 19th, 1946

Rotary Total Depth 3810'

CASING RECORD

1025' 8 5/8" Surface Casing
Cemented 400 sacks cement

LOG

| | |
|-----------|----------------|
| 0- 375 | Shale |
| 375- 550 | Sand |
| 550- 585 | Red Bed |
| 585- 850 | Red Shale |
| 850-1020 | Red Bed |
| 1020-1050 | Anhydrite |
| 1050-1230 | Shale |
| 1230-1675 | Shale & Shells |
| 1675-1780 | Shale |
| 1780-2450 | Lime |
| 2450-2495 | Shale |
| 2495-2730 | Lime |
| 2730-3025 | Shale & Shells |
| 3025-3085 | Lime |
| 3085-3220 | Lime & Shale |
| 3220-3358 | Lime |
| 3358-3440 | Shale |
| 3440-3660 | Lime |
| 3660-3707 | Shale |
| 3707-3733 | Shale & Lime |
| 3733-3810 | Lime |

FORMATION TOPS

| | |
|---------------|------|
| Lansing | 3418 |
| Arbuckle..... | 3718 |

PRODUCTION

None --- Dry hole

Total Depth 3810'

PLUGGING
WELL 2 20 16W
LOG PAGE 78 OF 32

