


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Flat

Pawnee County. Sec. 2 Twp. 20S Rge. 16 (W)  
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines C-NW NW SW  
Lease Owner Sunray Oil Corporation  
Lease Name Fleske Well No. 2  
Office Address Box 195, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed August 20 19 45  
Application for plugging filed August 8 19 51  
Application for plugging approved August 9 19 51  
Plugging commenced September 1 19 51  
Plugging completed September 9 19 51  
Reason for abandonment of well or producing formation Well produced a considerable amount of SW but not enough oil to pay for cost of SWD.  
If a producing well is abandoned, date of last production January 8 19 51  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Stough  
Producing formation Arbuckle Depth to top 3694' Bottom 3734' Total Depth of Well 3734' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From  | To    | Size             | Put In         | Pulled Out    |
|-----------|---------|-------|-------|------------------|----------------|---------------|
| Arbuckle  | Oil     | 3694' | 3734' | 8-5/8"<br>5 1/2" | 1025'<br>3739' | None<br>2613' |
|           |         |       |       |                  |                |               |
|           |         |       |       |                  |                |               |
|           |         |       |       |                  |                |               |
|           |         |       |       |                  |                |               |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sanded hole from 3734' to 3720' and ran 5 sax of cement. Mudded hole to 270', set 20' rock bridge and ran 15 sax of cement. Mudded hole to 30' and ran 10 sax of cement. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Sunray Oil Corporation  
Address Box 195, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
W. E. Westbrook, Jr. (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. E. Westbrook, Jr.  
Box 195, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 19 day of September, 19 51.

My commission expires 4-19-52

PLUGGING 28-3278-s 4-50-10M  
FILE SEC 2 Twp 20 R 16 W  
BOOK PAGE 19 LINE 27

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 20 1951  
CONSERVATION DIVISION  
Wichita, Kansas

9-20-1951

WELL LOG

A. W. Fleske #2

Location:

C-NW NW SW Sec. 2, 20S, 16W,  
Pawnee County, Kansas.

Lease Owner:

Sunray Oil Corporation  
Completed: 8/20/45.

| <u>Formation</u> | <u>Thickness</u> | <u>Depth</u> |
|------------------|------------------|--------------|
| Cellar           | 0                | 7            |
| Shale Sand       | 103              | 110          |
| Shale            | 140              | 250          |
| Shale & Shells   | 143              | 393          |
| Sand & Shale     | 67               | 460          |
| Sand             | 92               | 552          |
| Red Bed          | 78               | 620          |
| Shale & Red Bed  | 401              | 1021         |
| Anhydrite        | 4                | 1025         |
| Anhydrite        | 20               | 1045         |
| Shale & Red Bed  | 55               | 1200         |
| Shale & Shells   | 265              | 1465         |
| Salt             | 50               | 1515         |
| Salt & Shale     | 225              | 1740         |
| Shale            | 40               | 1780         |
| Shale & Shells   | 50               | 1830         |
| Lime & Shale     | 70               | 1900         |
| Lime             | 25               | 1925         |
| Lime & Shale     | 245              | 2170         |
| Lime & Shale     | 25               | 2190         |
| Lime             | 55               | 2250         |
| Lime & Shale     | 50               | 2300         |

| <u>Formation</u> | <u>Thickness</u> | <u>Depth</u> |
|------------------|------------------|--------------|
| Shale            | 15               | 2315         |
| Lime             | 40               | 2355         |
| Lime & Shale     | 55               | 2410         |
| Shale & Shells   | 15               | 2425         |
| Lime             | 40               | 2465         |
| Lime             | 25               | 2490         |
| Shale & Shells   | 160              | 2650         |
| Shale & Shells   | 160              | 2810         |
| Lime             | 30               | 2840         |
| Shale            | 30               | 2870         |
| Lime & Shale     | 55               | 2925         |
| Shale & Shells   | 95               | 3020         |
| Lime & Shale     | 127              | 3147         |
| Lime & Shale     | 43               | 3190         |
| Lime             | 89               | 3279         |
| Lime Broken      | 85               | 3364         |
| Shale & Lime     | 39               | 3403         |
| Lime             | 12               | 3415         |
| Lime             | 238              | 3653         |
| Shale            | 11               | 3664         |
| Lime             | 63               | 3727         |
| Arbuckle Lime    | 10               | 3737         |

SEP 20 1951

I, W. E. Westbrook, Jr. being first duly sworn, on oath state that I have knowledge of the facts and matter herein set forth and that the same are true and correct.

*W. E. Westbrook, Jr.*

Sworn and subscribed to before me this 19th day of September, 1951.

FILE SEC 2 10-16-51  
BOOK PAGE 101 LINE 27

*J. K. Kerpateen*  
Notary Public

My Commission expires Mar. 26, 1953