

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-069-20341-00-01
 Spot: S2SWNWSE Sec/Twnshp/Rge: 18-28S-29W
1570 feet from S Section Line, 2310 feet from E Section Line
 Lease Name: JOHN KOEHN Well #: 1-18(SE)
 County: GRAY Total Vertical Depth: 5655 feet

Operator License No.: 5316
 Op Name: FALCON EXPLORATION, INC.
 Address: 125 N MARKET STE 1252
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3315		WITH 2 SX CMT
CIBP		3475		WITH 2 SX CMT
CIBP		3510		
PROD	4.5	3652	2136	WITH 215 SX CMT
SURF	8.625	1871		WITH 825 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/25/2018 12:00 PM
 Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING
 Proposal Rcvd. from: RENE RESENDIZ Company: FALCON EXPLORATION Phone: (620) 546-4752

Proposed Plugging Method: CIBP @ 3475' WITH 2 SX CMT. CIBP @ 3315' WITH 2 SX CMT. PLUG AT 1900' WITH 15 SX GEL & 50 SX CMT. PLUG AT 800' WITH 50 SX CMT. PLUG AT 400' WITH 30 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
 Date/Time Plugging Completed: 01/25/2018 3:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 3475' WITH 2 SX CMT. CIBP @ 3315' WITH 2 SX CMT. 1ST PLUG AT 1900' WITH 50 SX CMT. 2ND PLUG AT 800' WITH 50 SX CMT. 3RD PLUG AT 400' WITH 30 SX CMT. 4TH PLUG AT 40' WITH 20 SX CMT. TOP OFF WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3546	3552		
3523	3552		
3364	3369		

Remarks: USED 60/40 POZMIX 4% GEL BY GLOBAL.

Plugged through: CSG

District: 01

Signed

[Signature]
 (TECHNICIAN)

RECEIVED
 JAN 29 2018
 KCC DODGE CITY

INVOICED
 MAR 02 2018