

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-25085-00-00
Spot: E2W2NWNW Sec/Twnshp/Rge: 17-20S-13W
660 feet from N Section Line, 470 feet from W Section Line
Lease Name: D. ROACH Well #: 1-17
County: BARTON Total Vertical Depth: 3675 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3675		150 SX
SURF	8.625	789		335 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/15/2018 1:00 PM
Plug Co. License No.: 8253 Plug Co. Name: G & L WELL SERVICE, INC.
Proposal Rcvd. from: ROB LONG Company: F. G. HOLL COMPANY L.L.C. DBA Phone: (620) 793-0915

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 10 sx gel and 500 # hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/15/2018 12:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1400' and 900'. Ran tubing to 3396' and pumped 10 sx gel followed by 40 sx cement w/100 # hulls. Pulled tubing to 1400' and pumped 40 sx cement. Pulled tubing to 900' and pumped 45 sx cement. Pulled tubing to 300'. Circulated cement to surface with 220 sx cement on the casing and the surface pipe. Pulled tubing and topped off with 5 sx cement.

GPS: 38.31749 -098.79137

Perfs:

Top	Bot	Thru	Comments
3530	3540		
3527	3544		
3472	3477		
3388	3392		
3366	3371		
3310	3392		

Remarks: BASIC ENERGY INC.

Plugged through: TBG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

FEB 16 2018