

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-047-20131-00-00
Spot: NWSEWSW Sec/Twnshp/Rge: 9-24S-16W
547 feet from S Section Line, 4293 feet from E Section Line
Lease Name: COPPOC-RUDD Well #: 1
County: EDWARDS Total Vertical Depth: 4335 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4225		WITH 2 SX CMT
PROD	5.5	4334	1560	WITH 125 SX CMT
SURF	8.625	350		WITH 250 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/23/2018 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: ROB LONG Company: F.G. HOLL COMPANY Phone: (620) 793-0915

Proposed Plugging Method: CIBP @ 4225' WITH 2 SX CMT ON TOP. LOAD HOLE. CHECK WITH PRESSURE. IF OK USED CASING. IF NOT USE TUBING. PLUG AT 1110' WITH 10 SX GEL & 50 SX CMT. PLUG AT 380' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/23/2018 5:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

SET CIBP @ 4225' WITH 2 SX CMT ON TOP. PRESSURE TEST CASING TO 250#. 1ST PLUG AT 1120' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 380' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 25 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4273	4279	CSG	

RECEIVED
MAR 02 2018

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: CSG

District: 01

Signed Ken Scofield
(TECHNICIAN)

RECEIVED
FEB 12 2018
KCC DODGE CITY