

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-047-20442-00-00  
Spot: SWNESESE Sec/Twnshp/Rge: 11-24S-17W  
702 feet from S Section Line, 639 feet from E Section Line  
Lease Name: ENLOW-MILLER Well #: 1-11  
County: EDWARDS Total Vertical Depth: 4425 feet

Operator License No.: 5056  
Op Name: F. G. HOLL COMPANY L.L.C.  
Address: 9431 E CENTRAL STE 100  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4225		WITH 2 SX CMT
PROD	4.5	4424	0	WITH 150 SX CMT
SURF	8.625	251		WITH 225 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/26/2018 10:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: ROB LONG Company: F.G. HOLL COMPANY Phone: (620) 793-0915

Proposed Plugging Method: CIBP @ 4225' WITH 2 SX CMT. PERFORATE AT 1140'. SQUEEZE 50 SX CMT WITH HULLS. PERFORATE AT 500' & CIRCULATE CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/26/2018 2:30 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

SET CIBP @ 4225' WITH 2 SX CMT ON TOP. PERFORATE AT 1140' & 500'. TRIP IN HOLE WITH 2 3/8" TBG TO 1140'. PUMP 50 SX CMT WITH 200# HULLS IN LAST 25 SX CMT. PULL TBG TO 500' & PUMP 40 SX CMT TO SURFACE. PULL TBG OUT OF HOLE & TIE ONTO 4 1/2" CASING. PUMP 275 SX CMT TO FILL BACKSIDE & 4 1/2" CASING WITH CMT.

Perfs:

Top	Bot	Thru	Comments
4283	4354		
4273	4277		

**INVOICED**  
**MAR 02 2018**

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA HIGH FL\*\* USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: TBG

District: 01

Signed *Ken Scofield*  
(TECHNICIAN)

RECEIVED  
MAR 12 2018  
KCC DODGE CITY