

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-137-20734-00-00
Spot: NWSESWSW Sec/Twnshp/Rge: 21-4S-22W
540 feet from S Section Line, 940 feet from W Section Line
Lease Name: SCOTT Well #: 1
County: NORTON Total Vertical Depth: 3775 feet

Operator License No.: 34916 String Size Depth (ft) Pulled (ft) Comments
Op Name: FOURWINDS OIL CORPORATION PROD 4.5 3664 840 SX
Address: PO BOX 1063 SURF 8.625 216 120 SX
HAYS, KS 67601

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/10/2018 10:30 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: DAN WINDHOLZ Company: FOURWINDS OIL CORPORATION Phone: (785) 259-8403

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Production perforations: 3539' - 3593'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/10/2018 12:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 4 1/2" casing and pumped 250 sx cement w/300 # hulls. Pressured to 500 psi.
Hooked to 8 5/8" x 4 1/2" annulus and pressured to 300 psi immediately.
GPS: 39.68420N -099.81195W

Perfs:

Top	Bot	Thru	Comments
3591	3593		
3539	3546		
3526	3528		
3480	3482		
3462	3464		

INVOICED
MAR 02 2018

Remarks: QUALITY OILWELL TICKET # 630

Plugged through: CSG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

JAN 23 2018

Received
KANSAS CORPORATION COMMISSION

FEB 23 2018

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

JAN 23 2018