

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-145-21537-00-00  
Spot: S2SWSWNE Sec/Twnshp/Rge: 25-21S-16W  
2851 feet from S Section Line, 2295 feet from E Section Line  
Lease Name: WARD FEED YARD Well #: 1  
County: PAWNEE Total Vertical Depth: 3974 feet

Operator License No.: 34402  
Op Name: GARAL, DONNA AND VINCENT INNON  
Address: 30-38 48 ST  
ASTORIA, NY 11103

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3800		WITH 2 SX CMT
PROD	5.5	3950	2880	WITH 125 SX CMT
SURF	8.625	973		WITH 410 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/26/2018 11:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: JASON DINGES Company: VJI NATURAL RESOURCES Phone: (785) 623-8060

Proposed Plugging Method: CIBP @ 3800' WITH 2 SX CMT. TEST CASING AFTER BRIDGE. PLUG AT 1000' WITH 15 SX GEL & 50 SX CMT. PLUG AT 450' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 01/29/2018 4:00 PM

KCC Agent: KEN SCOFIELD

Actual Plugging Report:

Perfs:

1/26/18: SET CIBP @ 3800' WITH 2 SX CMT ON TOP. PRESSURE TEST CASING TO 300 PSI. 1ST PLUG AT 1000' WITH 10 SX GEL & 50 SX CMT. RIG BROKE DOWN.  
1/29/18: TAG CMT AT 900'. PUMP ANOTHER 50 SX CMT. 2ND PLUG AT 450' WITH 40 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Top	Bot	Thru	Comments
3854	3858		

**INVOICED**  
**MAR 02 2018**

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: TBG

District: 01

Signed

Ken Scofield  
(TECHNICIAN)

RECEIVED  
FEB 12 2018  
KCC DODGE CITY