

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-25820-00-00
Spot: NENESESE Sec/Twnshp/Rgc: 22-19S-23W
1140 feet from S Section Line, 110 feet from E Section Line
Lease Name: BSB Well #: 1-22
County: NESS Total Vertical Depth: 4561 feet

Operator License No.: 9855
Op Name: GRAND MESA OPERATING COMPANY
Address: 1700 N WATERFRONT PKWY BLDG 600
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4390		
PC		1558		CEMENTED WITH 150 SX CMT 15 SX CMT CIRCULATED TO PIT.
PROD	5.5	4556	0	WITH 200 SX CMT
SURF	8.625	221		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/24/2018 10:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOHN JOHNSON Company: GRAND MESA OPERATING Phone: (620) 617-3357

Proposed Plugging Method: TIE ON 5 1/2" CASING & PUMP 50 SX CMT & HULLS. GEL SPACER TO 1550'. CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: NONE
Date/Time Plugging Completed: 01/24/2018 1:30 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

SQUEEZE PERFS WITH 50 SX CMT & 120# HULLS. PUMP 18 SX GEL SPACER TO 1550'. PUMP 150 SX CMT FROM 1550'-0'. PUMP 15 SX CMT DOWN BACKSIDE.

Perfs:

Top	Bot	Thru	Comments
4393	4403		
4379	4383		
4355	4360		

INVOICED
MAR 02 2018

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

RECEIVED
JAN 29 2018
KCC DODGE CITY

Signed _____

(TECHNICIAN)