

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-20967-00-00
Spot: W2NENESW Sec/Twnshp/Rge: 28-11S-24W
2310 feet from S Section Line, 3000 feet from E Section Line
Lease Name: ROGERS Well #: 28-111
County: TREGO Total Vertical Depth: 4140 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4119		150 SX
SURF	8.625	207		180 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/31/2018 8:00 AM
Plug Co. License No.: 33007 Plug Co. Name: RGN COMPANY, INC.
Proposal Rcvd. from: ROLAND NYP Company: HERMAN L. LOEB, LLC DBA Phone: (785) 737-3242

Proposed Plugging Method: Squeeze jobs 2009: 2094' - 2127' w/200 sx cement.
2013: 1728' - 1793' w/100 sx cement.
Production perforations: 4044' - 4046'.
Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/31/2018 2:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated 2 holes each at 2600' and 1200'. Ran tubing to 4018'. Quality Oilwell Cementing pumped 100 sx cement w/300 # hulls. Pulled tubing to 2606' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1506' and pumped 110 sx cement. Cement circulated. PTOH. Topped 4 1/2" casing with 25 sx cement. Hooked up to backside and pumped 15 sx cement pressured to 300 psi.
02/01/2018 - Topped off casing with 15 sx cement.

Perfs:

Top	Bot	Thru	Comments
4044	4046		

Remarks: QUALITY OILWELL CEMENTING

Plugged through: TBG

INVOICED
MAR 02 2018

District: 04

Signed



(TECHNICIAN)

CM

FEB 05 2018

Received
KANSAS CORPORATION COMMISSION

FEB 23 2018

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3