

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-28406-00-00
Spot: NWNESWNE Sec/Twnshp/Rge: 21-30S-16E
1398 feet from N Section Line, 1761 feet from E Section Line
Lease Name: RENN Well #: LO-9
County: WILSON Total Vertical Depth: 862 feet

Operator License No.: 35122
Op Name: LAKE SHORE OPERATING, LLC
Address: 23 1/2 E. MADISON AVE SUITE A
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	33		9 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/21/2017 12:00 PM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Revd. from: TOM GILLMAN Company: LAKE SHORE OPERATING Phone: (620) 380-6780

Proposed Plugging Method: Run in 1" to well T.D of 852'. Put 75' plug on bottom. Place gel to 550' then place cement from 550' to 500'. Set more gel from 500' to 250' then cement from 250' to surface.

Plugging Proposal Received By: ALAN DUNNING Witness Type: NONE
Date/Time Plugging Completed: 11/21/2017 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

A cement string was lowered to TD of 852'. 2 sacks of gel were pumped and then 10 sacks of cement. The cement string was pulled to 500 ft and 10 sacks of cement spotted. The cement string was pulled to 250 ft and the well filled to surface with 40 sacks of cement. A total of 60 sacks of portland cement were used to plug well.

RECEIVED
KCC DIST # 3
FEB 12 2018
CHANUTE, KS

AD

INVOICED
MAR 02 2018

Remarks:

Plugged through: OH

District: 03

Signed

Alan Dunning
(TECHNICIAN)