

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-025-21054-00-00
Spot: NWNWSENE Sec/Twnshp/Rge: 34-34S-24W
3713 feet from S Section Line, 991 feet from E Section Line
Lease Name: GABBERT Well #: 1-34
County: CLARK Total Vertical Depth: 5950 feet

Operator License No.: 6113
Op Name: LANDMARK RESOURCES, INC.
Address: 4900 WOODWAY DR SUITE 880
HOUSTON, TX 77056

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5530		WITH 2 SX CMT
PROD	4.5	5821	2120	WITH 175 SX CMT
SURF	8.625	561		WITH 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/25/2018 9:30 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Revd. from: MARLIN CLARK Company: SARGENT LILLARD CASING PULL Phone: (316) 755-3523

Proposed Plugging Method: CIBP @ 5530' WITH 2 SX CMT. PLUG AT 930' WITH 10 SX GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 250' WITH 30 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE
Date/Time Plugging Completed: 01/25/2018 1:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

SET CIBP @ 5530' WITH 2 SX CMT. CUT CASING AT 2545'. PULLED 8 JOINTS & HUNG UP, RE-CUT AT 2120' & PULLED TO 930'. LOADED HOLE WITH MUD. 1ST PLUG AT 930' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5672	5680		
5594	5618		
5581	5586		

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

INVOICED

MAR 02 2018

District: 01

Signed Larry D. Harris
(TECHNICIAN)

RECEIVED
JAN 29 2018
KCC DODGE CITY