

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-171-21216-00-00
Spot: SWNENENE Sec/Twnshp/Rge: 8-16S-34W
345 feet from N Section Line, 645 feet from E Section Line
Lease Name: TUCKER Well #: 1-8
County: SCOTT Total Vertical Depth: 4850 feet

Operator License No.: 6113
Op Name: LANDMARK RESOURCES, INC.
Address: 4900 WOODWAY DR SUITE 880
HOUSTON, TX 77056

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	261		WITH 185 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/27/2018 9:00 AM
Plug Co. License No.: 6039 Plug Co. Name: L. D. DRILLING, INC.
Proposal Rcvd. from: CHRIS Company: L. D. DRILLING, INC. Phone: (620) 793-3051

Proposed Plugging Method: 1ST PLUG AT 2530' WITH 50 SX CMT. 2ND PLUG AT 1530' WITH 80 SX CMT. 3RD PLUG AT 750' WITH 50 SX CMT. 4TH PLUG AT 300' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: NONE
Date/Time Plugging Completed: 01/27/2018 11:00 AM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

1ST PLUG AT 2530' WITH 50 SX CMT. 2ND PLUG AT 1530' WITH 80 SX CMT. 3RD PLUG AT 750' WITH 50 SX CMT. 4TH PLUG AT 300' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Perfs:

INVOICED
MAR 02 2018

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY HURRICANE.

Plugged through: DP

District: 01

Signed _____
(TECHNICIAN)
SA

RECEIVED
JAN 29 2018
KCC DODGE CITY