

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-207-02500-00-00  
Spot: NWSWSE Sec/Twshp/Rgc: 32-23S-17E  
927 feet from S Section Line, 2445 feet from E Section Line  
Lease Name: NELSON Well #: 3  
County: WOODSON Total Vertical Depth: 895 feet

Operator License No.: 30661  
Op Name: L & B CRUDE, INC.  
Address: 714 S. MAIN ST. P.O. BOX 117  
YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	2	854		
PROD	1	854	854	
PROD	2	894		20 SX
SURF	6	40		10 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/18/2017 12:00 PM  
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.  
Proposal Rcvd. from: MARK LEEDY Company: L & B CRUDE, INC Phone: (620) 490-0034

Proposed Plugging Method: Run 1" inside 2" to bottom and spot 100ft of cement, 100ft at 500ft depth, and from 250ft to surface. Run 1" down outside of 2" to depth of 200ft and cement to surface.

Plugging Proposal Received By: ALAN DUNNING Witness Type: NONE  
Date/Time Plugging Completed: 12/18/2017 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A one inch cement string was lowered to 890 ft inside the production pipe. The well was then pumped full from btm to top thru the cement string with cement, both inside and outside the 2 inch production pipe. The cement string was pulled and the well topped off with 5 sacks of cement. The operator came back after the cement settled and topped the well off with an additional 5 sacks. A total of 35 sacks of portland cement were used to plug well.

Perfs:

Top	Bot	Thru	Comments
864	876		

RECEIVED  
KCC DIST # 3  
FEB 21 2018  
CHANUTE, KS

AD

INVOICED

MAR 09 2018

Remarks:

Plugged through: CSG

District: 03

Signed

Alan Dunning  
(TECHNICIAN)