

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-207-02501-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 32-23S-17E
632 feet from S Section Line, 2449 feet from E Section Line
Lease Name: NELSON Well #: 2
County: WOODSON Total Vertical Depth: 893 feet

Operator License No.: 30661
Op Name: L & B CRUDE, INC.
Address: 714 S. MAIN ST. P.O. BOX 117
YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	2	842		
PROD	1	842	842	
PROD	2	892		20 SX
SURF	6	40		10 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/18/2017 12:00 PM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: MARK LEEDY Company: L & B CRUDE, INC Phone: (620) 490-0034

Proposed Plugging Method: Run 1" inside 2" to bottom and spot 100ft of cement, 100ft at 500ft depth, and from 250ft to surface. Run 1" down outside of 2" to depth of 200ft and cement to surface.

Plugging Proposal Received By: ALAN DUNNING Witness Type: NONE
Date/Time Plugging Completed: 12/18/2017 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A one inch cement string was lowered to 890 ft inside the 2 inch production pipe. The well was then pumped full from btm to top thru the cement string with cement, both inside and outside the 2 inch production pipe. The cement string was pulled and the well topped off with 5 sacks of cement. The operator came back after cement settled and topped with 2 additional sacks of cement. A total of 32 sacks of portland cement were used to plug well.

Perfs:

Top	Bot	Thru	Comments
860	876		

RECEIVED
KCC DIST #3
FEB 21 2018
CHANUTE, KS
AD
INVOICED
MAR 02 2018

Remarks:

Plugged through: CSG

District: 03

Signed

Alan Dunning
(TECHNICIAN)