

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-207-02502-00-00
Spot: SWSWSE Sec/Twushp/Rge: 32-23S-17E
364 feet from S Section Line, 2290 feet from E Section Line
Lease Name: NELSON Well #: 1
County: WOODSON Total Vertical Depth: 930 feet

Operator License No.: 30661
Op Name: L & B CRUDE, INC.

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	2	860		20 SX
PROD	4.5	930	860	
SURF	6	40		10 SX

Address: 714 S. MAIN ST. P.O. BOX 117
YATES CENTER, KS 66783

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/18/2017 12:00 PM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Revd. from: MARK LEEDY Company: L & B CRUDE, INC Phone: (620) 490-0034

Proposed Plugging Method: Run 1" inside 2" to bottom and spot 100ft of cement, 100ft at 500ft depth, and from 250ft to surface. Run 1" down outside of 2" to depth of 200ft and cement to surface.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE
Date/Time Plugging Completed: 12/18/2017 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A one inch cement string was lowered to 925 ft inside the 2 inch production pipe. The well was then pumped full from btm to top thru the cement string with cement, both inside and outside the 2 inch production pipe. The cement string was pulled and the well topped off with cement. The operator came back and topped with an additional 3 sacks of cement. A total of 105 sacks of portland cement were used to plug well.

Perfs:

Top	Bot	Thru	Comments
861	871		

RECEIVED
KCC DIST #3
FEB 21 2018
CHANUTE, KS

AD

INVOICED

MAR 02 2018

Remarks:

Plugged through: CSG

District: 03

Signed Alan Dunning
(TECHNICIAN)