

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-00419-00-01
Spot: NWSEENW Sec/Twnshp/Rge: 23-12S-15W
4306 feet from S Section Line, 3015 feet from E Section Line
Lease Name: ELSASSER Well #: 1
County: RUSSELL Total Vertical Depth: 3146 feet

Operator License No.: 6246
Op Name: BENNETT & SCHULTE OIL CO., A GEN
Address: PO BOX 329
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3146		150 SX
SURF	8.625	182		150 SX

Well Type: EOR UIC Docket No: E26178.1 Date/Time to Plug: 02/13/2018 12:30 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: JOE ROTH Company: BENNETT & SCHULTE OIL CO. Phone: (785) 483-2721

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/400 # hulls.
Squeezed at 362' - 620' w/365 sx cement.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/14/2018 7:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 925' and 1350'. Ran tubing to 2800' and pumped 100 sx cement. Good returns. Started to lose circulation near the end of pumping cement. Pulled tubing to 1400' and pumped 100 sx cement w/100 # hulls. Had circulation then lost circulation. Pulled tubing to 600' and pumped 70 sx cement w/100 # hulls. Circulated cement to the pit. POOH. Hooked to braden head and pumped about 1/8 bbls at 200 psi. Filled casing with 10 sx cement.
02/14/2018 - Cement down 3-4 seconds. Will top off after cutting head off.

GPS: 38.99913 -098.95650

Perfs:


Top	Bot	Thru	Comments
2857	2912		

Remarks: QUALITY CEMENTING TICKET # 651

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

FEB 23 2018

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

INVOICED
MAR 01 2018