

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-083-10130-00-01  
Spot: NWNWSWNE Sec/Twnshp/Rge: 15-22S-25W  
3642 feet from S Section Line, 2315 feet from E Section Line  
Lease Name: KLINE Well #: 2  
County: HODGEMAN Total Vertical Depth: 4690 feet

Operator License No.: 3273  
Op Name: HERMAN L. LOEB, LLC  
Address: PO BOX 838  
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4500		WITH 2 SX CMT
CIBP		4587		
PROD	5.5	4689	0	WITH 100 SX CMT
SURF	8.625	555		WITH 350 SX CMT

Well Type: EOR UIC Docket No: E07630.3 Date/Time to Plug: 02/07/2018 9:00 AM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
Proposal Rcvd. from: TRACY HOLLIS Company: HERMAN L LOEB Phone: (620) 792-0527

Proposed Plugging Method: SET CIBP @ 4500' WITH 2 SX CMT. PERFORATE AT 1600'. PUMP 40 SX CMT THEN 40 SX CMT WITH HULLS. PERFORATE AT 600' & CIRCULATE CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: PARTIAL  
Date/Time Plugging Completed: 02/07/2018 11:20 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

BP @ 4597'. SET CIBP @ 4500' WITH 2 SX CMT. PERFORATED AT 1600'. TIED ONTO CASING & PUMPED 40 SX CMT THEN 40 SX CMT WITH 150# HULLS. DISPLACED WITH 32 BBL MUD. PERFORATED AT 600'. TIED ONTO CASING & CIRCULATED CMT TO SURFACE WITH 200 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4620	4625		
4590	4595		
4562	4578		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENT.

Plugged through: CSG

District: 01

Signed

(TECHNICIAN)

RECEIVED  
FEB 12 2018  
KCC DODGE CITY

INVOICED

FEB 02 2018