

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-21641-00-01
Spot: NWSEW Sec/Twnshp/Rge: 27-17S-15W
3630 feet from S Section Line, 3630 feet from E Section Line
Lease Name: SCHREIBER-MANETH Well #: 1
County: BARTON Total Vertical Depth: 3563 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 8411 PRESTON RD STE 800
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3559		475 SX
SURF	8.625	292		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/26/2018 9:00 AM
Plug Co. License No.: 33385 Plug Co. Name: J & M WELL SERVICING, INC.
Proposal Rcvd. from: BRENT HOMEIER Company: MAI OIL OPERATIONS, INC. DBA Phone: (785) 445-2353

Proposed Plugging Method: Ordered 275 sx 60/40 pozmix 4% gel cement w/10 sx gel.
01/29/2018 - Ordered 100 sx 60/40 pozmix 4% gel cement.
DV Tool at 1052' w/375 sx cement.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/26/2018 12:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 1450'. Ran tubing to 3500' and pumped 10 sx gel followed by 40 sx cement.
Pulled tubing to 1480' and pumped 135 sx cement. Circulated cement to pit. POOH. Pumped 75 sx cement. Cement would not load.
01/29/2018 - Ran tubing and tagged at 730'. Pulled 1 joint of tubing out and pumped 50 sx cement. Circulated cement to pit. POOH. Topped off with 10 sx cement. Hole stayed full.
GPS: 38.54654 -098.97233

Perfs:

Top	Bot	Thru	Comments
3559	3563		

INVOICED

MAR - 8 2018

Remarks: QUALITY CEMENTING TICKET # 460 AND 461.

Plugged through: TBG

District: 04

Signed

Ray Dinkel

Received
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

CM

FEB 23 2018

CONSERVATION DIVISION
WICHITA, KS

JAN 30 2018

Form CP-2/3