

1060208

TO: STATE CORPORATION COMMISSION

API NUMBER 15-097-21,453 - 0000
SE/4 SEC. 15, T 30 S, R 16 W

CONSERVATION DIVISION - PLUGGING SECTION 1250 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1250 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME ED PERRY-ROBBINS WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY KIOWA 162.18

OPERATOR LICENSE # 31297 5/18 WELL TOTAL DEPTH 4990 FEET

OPERATOR: JAMES B. READ OPERATING PRODUCTION CSG: SIZE @ ' WITH SX

NAME AND PO BOX 638 SURFACE CASING: SIZE 10 1/4" @ 326' WITH SX

ADDRESS ARDMORE, OK 73402 CONDUCTOR CSG: SIZE 20" @ 40'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR VAL ENERGY LICENSE NUMBER 5822

ADDRESS PO BOX 116 WICHITA, KS 67201

COMPANY TO PLUG AT: HOUR: 4:15 AM DAY: 18 MONTH: 05 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM SKIP

(COMPANY NAME) VAL ENERGY (PHONE) 316-263-6688

WERE:

1ST PLUG AT 802' WITH 50 SX CEMENT. 2ND PLUG AT 350' WITH 75 SX CEMENT.

3RD PLUG AT 40' WITH 20 SX CEMENT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY SCOTT ALBERG

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 7:15 AM DAY: 18 MONTH: 05 YEAR: 2000

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 802' WITH 50 SX CEMENT. 2ND PLUG AT 350' WITH 75 SX CEMENT.

3RD PLUG AT 40' WITH 20 SX CEMENT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

RECEIVED
STATE CORPORATION COMMISSION

JUL 06 2000

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.) CONSERVATION DIVISION
Wichita, Kansas

I (DID NOT) OBSERVE THIS PLUGGING.

INVOICED
SIGNED
DATE 7/10/00
INV. NO. 1060029

Michael J. Mason
(TECHNICIAN)

FORM CP-2/3