

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-22361-00-01
Spot: W2E2W2SW Sec/Twnshp/Rge: 30-10S-24W
1320 feet from S Section Line, 4450 feet from E Section Line
Lease Name: GANO Well #: 1
County: GRAHAM Total Vertical Depth: 4102 feet

Operator License No.: 6861
Op Name: RON'S OIL OPERATIONS INC
Address: 1889 200TH AVE
PENOKEE, KS 67659

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4090		150 SX
SURF	8.625	272		170 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/31/2018 8:00 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: DALE POE Company: RON'S OIL OPERATIONS INC DBA Phone: (785) 475-3422

Proposed Production Perforations: 3850' - 3853'
Plugging Backside full of cement.
Method: Ordered 275 sx 60/40 pozmix 4% gel cement w/1200 # gel and 300 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/31/2018 6:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

Ran tubing to 3816'. Quality Oilwell Cementing pumped 1200 # gel followed by 50 sx cement w/300 # hulls. Pulled tubing to 2130' and pumped 100 sx cement. Pulled tubing to 1033' and pumped 105 sx cement. Cement circulated. PTOH. Topped off 5 1/2" casing with 15 sx cement. Backside full of cement.

Remarks: QUALITY OILWELL CEMENTING

Plugged through: TBG

INVOICED
MAR - 7 2018

District: 04

Signed Richard Williams
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

FEB 23 2018

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

FEB 05 2018