

FO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-20524-00-01

Spot: SEWSE Sec/Twnshp/Rge: 29-23S-11E
1650 feet from S Section Line, 1650 feet from E Section Line

Lease Name: EDWARDS Well #: 3
County: GREENWOOD Total Vertical Depth: 2063 feet

Operator License No.: 7564
Op Name: R & W ENERGIES, A GENERAL PARTN
Address: 403 N. MYRTLE
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1995		
SURF	8.625	46		

Well Type: EOR UIC Docket No: E22195.1 Date/Time to Plug: 02/15/2018 1:00 PM
Plug Co. License No.: 99973 Plug Co. Name: ELITE CEMENTING AND ACID SERVICE, LLC
Proposal Rcvd. from: BRYAN MARSHALL Company: Phone: (620) 583-4785

Proposed Plugging Method: Per KCC

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/15/2018 5:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Ran tubing to 1870', pumped 20 sxs cement, pulled tubing to 900', pumped 10 sxs cement, pulled tubing to 250', pumped 50 sxs cement to surface, casing shot @ 900' & 250', gel spacers between cement spacers.

Perfs:

RECEIVED
KCC DIST # 3
FEB 19 2018
CHANUTE, KS
MH

INVOICED
MAR - 6 2018

Remarks:
Plugged through: TBG

District: 03

Signed Michael Heffern
(TECHNICIAN)

810 E 7th
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



~~15-07320524~~ 15-07320524
 Cement or Acid Field Report
 Ticket No. 3756
 Foreman Steve Mead
 Camp Eureka

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
2-15-18	1163	Lucky Edward # 3				Greenwood	KS
Customer Marshall Oil LLC			Safety Meeting	Unit #	Driver	Unit #	Driver
Mailing Address P.O. Box 389				102	Rick		
City Eureka				110	Dave		
State KS							
Zip Code 67045							

Job Type PTA old well Hole Depth _____ Slurry Vol. _____ Tubing 2 3/8 1870'
 Casing Depth _____ Hole Size _____ Slurry Wt. _____ Drill Pipe _____
 Casing Size & Wt. 4 1/2 Cement Left in Casing _____ Water Gal/SK _____ Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety Meeting. Rig up to 2 3/8 Tubing Break Circulation w/ Fresh Water. Pump 250# Gel Spacer. Plug well as follow.

20sk AT 1870'

10sk N 900'

50sk - 250 to Surface

Total 80sk 60/40 Permox w/ 4% Gel

Job Complete

Thank You

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C-05-2	1	Pump Charge	500.00	500.00
C-107	-	Mileage N/L	-	-
C-203	80 sks	60/40 Permox Cement	12.75	1020.00
C-206	275 ^{lb}	Gel 4%	.20	55.00
C-206	250 [#]	Gel Spacer	.20	50.00
C-214	20 [#]	Hulls	.45	9.00
C-108-A	3.44 Ton	Ton mileage bulk Truck	M/L	200.00
<div style="border: 1px solid black; border-radius: 50%; padding: 10px; display: inline-block;"> 0% (98.58) 41872.91 </div>				
			Subtotal	1834.00
			Sales Tax	137.55
Authorization <u>Bryan Marshall</u> Title <u>Co. Rep.</u>			Total	1971.55

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.