

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-01245-00-00
Spot: SESWSENE Sec/Twnshp/Rge: 2-26S-8E
2880 feet from S Section Line, 700 feet from E Section Line
Lease Name: HULL A AND B Well #: W-10
County: GREENWOOD Total Vertical Depth: 2436 feet

Operator License No.: 5394
Op Name: ABDERHALDEN, R. R.
Address: 100 S. MAIN, STE 510
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2403		100 SX
SURF	8.63	105		75 SX

Well Type: EOR UIC Docket No: _____ Date/Time to Plug: 03/15/2018 12:00 PM
Plug Co. License No.: 5656 Plug Co. Name: R.R.A., INC.
Proposal Rcvd. from: DWAIN STOUT Company: _____ Phone: (316) 640-9072

Proposed Plugging Method: Set 50 ft cement plug at TD. Shoot off casing at 1300 ft. Set 50 ft cement plug at 1300 ft. Cement from 150 ft to surface.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: NONE
Date/Time Plugging Completed: 03/15/2018 4:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report: _____ Perfs: _____

Ran tubing to 2280', pumped 15 sxs cement, pulled tubing to 1007', pumped 20 sxs cement, pulled tubing to 150', pumped 95 sxs cement to surface, casing shot @ 150' & 1007', gel spacers between ce,

RECEIVED
KCC DIST # 3
MAR 19 2018
CHANUTE, KS

MH

INVOICED
APR 20 2018

Remarks:
Plugged through: TBG

District: 03

Signed *Michael Heffern*
(TECHNICIAN)

15-073-01245 00 00

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. **3706**
 Foreman Rick Ledford
 Camp Eureka KS

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
3-15-18	1046	Hall A+G 61" 10	2	26	8	OW	KS
Customer	Mailing Address	City	State	Zip Code	Safety Meeting	Unit #	Driver
R.R.A Inc.	100 S. Main St. Ste 510	Wichita	KS	67202	DL AD JH AM	102	Rick L.
						110	Jason H.
						141	Allen B.
						121	Craig M.

Job Type P.T.A old well Hole Depth _____ Slurry Vol. _____ Tubing 2 3/8"
 Casing Depth _____ Hole Size _____ Slurry Wt. 14" Drill Pipe _____
 Casing Size & Wt. _____ Cement Left in Casing _____ Water Gal/SK _____ Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety meeting. Rig up to 2 3/8" tubing. Plugging orders as follows:
15 SKS @ 2280'
20 SKS @ 1007'
95 SK @ 18' to surface

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C105	1	Pump Charge	750.00	750.00
C107	15	Mileage	3.95	59.25
C203	130 SKS	60/40 Permox cement	12.75	1657.50
C206	450"	490 gal	.20	90.00
C206	400"	gel spacers	.20	80.00
C214	20"	hulls	.45	9.00
C102A	5.60	for mileage back truck	m/c	345.00
C113	2 1/2	80 BY WAC. TRK	85.00	212.50
C227	3000 gals	city water	10.00/1000	30.00
590 < 113.19 >				
\$ 3201.95				
			Subtotal	3233.25
			Sales Tax	242.49

Authorization by Devin Sturt Title _____ Total 3475.74

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.