

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-25988-00-00
Spot: SESWNWNE Sec/Twnshp/Rge: 22-20S-22W
1160 feet from N Section Line, 2015 feet from E Section Line
Lease Name: HCH Well #: 1-22
County: NESS Total Vertical Depth: 4427 feet

Operator License No.: 4058 String Size Depth (ft) Pulled (ft) Comments
Op Name: AMERICAN WARRIOR, INC. SURF 8.625 210 WITH 150 SX CMT
Address: PO BOX 399
GARDEN CITY, KS 67846

Well Type: DH UIC Docket No: Date/Time to Plug: 02/22/2018 4:00 PM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: 1ST PLUG AT 1500' WITH 50 SX CMT. 2ND PLUG AT 660' WITH 80 SX CMT. 3RD PLUG AT 240' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE
Date/Time Plugging Completed: 02/22/2018 6:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

1ST PLUG AT 1500' WITH 50 SX CMT. 2ND PLUG AT 660' WITH 80 SX CMT. 3RD PLUG AT 240' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY SWIFT SERVICES.


Plugged through: DP

INVOICED

APR 20 2018

District: 01

Signed



(TECHNICIAN)

RECEIVED
FEB 26 2018
KCC DODGE CITY

