

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-25989-00-00
Spot: NWSWSESE Sec/Twnshp/Rge: 35-20S-22W
600 feet from S Section Line, 1000 feet from E Section Line
Lease Name: DEANNA Well #: 1-35
County: NESS Total Vertical Depth: 4360 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	212		WITH 150 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 02/12/2018 11:00 PM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: GALEN GASCHLER Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: 1ST PLUG AT 1380' WITH 50 SX CMT. 2ND PLUG AT 570' WITH 80 SX CMT. 3RD PLUG AT 270' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: NONE
Date/Time Plugging Completed: 02/13/2018 1:00 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

Perfs:

1ST PLUG AT 1380' WITH 50 SX CMT. 2ND PLUG AT 570' WITH 80 SX CMT. 3RD PLUG AT 270' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY SWIFT.

Plugged through: DP

District: 01

Signed

K. Sullivan

(TECHNICIAN)

RECEIVED
FEB 16 2018

KCC DODGE CITY

MS

578

INVOICED

APR 20 2018