

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-033-21179-00-00
Spot: SESWSWSE Sec/Twnshp/Rge: 2-33S-16W
303 feet from S Section Line, 2226 feet from E Section Line
Lease Name: J. LENERTZ Well #: 1-2
County: COMANCHE Total Vertical Depth: 5547 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5175		WITH 2 SX CMT
PROD	5.5	5547	2830	WITH 150 SX CMT
SURF	8.625	590		WITH 300 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 02/19/2018 11:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: CIBP @ 5175' WITH 2 SX CMT. PLUG AT 800' WITH 10 SX GEL & 75 SX CMT. PLUG AT 280' WITH 30 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/20/2018 9:00 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5175' WITH 2 SX CMT. 1ST PLUG AT 800' WITH 10 SX GEL & 75 SX CMT. 2ND PLUG AT 280' WITH 30 SX CMT. 3RD PLUG AT 40'. PUMPED LAST 30 SX CMT BUT DID NOT CIRCULATE. CMT CAME TO APPROXIMATELY 30' FROM SURFACE. 2/20/18: TOPPED OFF WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5228	5236		

INVOICED
APR 20 2018

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed _____

(TECHNICIAN)

RECEIVED
MAR - 5 2018
KCC DODGE CITY

Form CP-2/3

12/MS