

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-109-21526-00-00
Spot: SENEWSW Sec/Twnshp/Rge: 22-14S-35W
949 feet from S Section Line, 1004 feet from W Section Line
Lease Name: DIRKS Well #: 1-22
County: LOGAN Total Vertical Depth: 4790 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4786		150 SX
SURF	8.625	211		170 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/01/2018 8:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: OCTAVIO MORALES Company: AMERICAN WARRIOR, INC. DBA Phone: (620) 275-2963

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 1500 # gel and 600 # hulls.
8 5/8" surface casing set at 211' w/170 sx cement.
5 1/2" production casing set at 4786' w/150 sx cement.
Port collar set at 2446' was not cemented.
TD 4790'.
Perforations: 3910' - 3922', 4051' - 4056' and 4268' - 4274'.
Well is non-commercial.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/01/2018 12:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Excel Wireline set CIBP at 3900' w/5 sx cement on top. Calculated casing recovery at 2000'. Operator requested casing cut below port collar. Cut casing at 2530'. Reciprocated casing and could not pull. Perforated 5 1/2" casing at 2493'. Ran tubing to 2480' and pumped 300 # gel followed by 50 sx cement w/200 # hulls. Pulled tubing from well. Cut 5 1/2" casing at 1430'. Casing free. Pulled one joint. Connected to 5 1/2" casing and pumped 12 sx gel followed by 100 sx cement w/250 # hulls. Lost circulation. Pulled casing to 240' and pumped 100 sx cement w/150 # hulls. Regained circulation. Cement to surface. Pulled casing to surface. Topped off casing with 5 sx cement. Casing standing full.

GPS: 38.81983N 101.20158W

Perfs:

Top	Bot	Thru	Comments
3910	4274		

KCC WICHITA
MAR 16 2018
RECEIVED

Remarks: AMERICAN WARRIOR INC. PULLING UNIT AND SWIFT SERVICES CEMENT. CEMENT TICKET # 31,326.
PLUGGED THROUGH CASING AND TUBING.

INVOICED

Plugged through: CSG

APR 20 2018

District: 04

Signed

Darrel Dipman

(TECHNICIAN)

C.M.

MAR 05 2018