

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-21663-00-00
Spot: NENENWSE Sec/Twnshp/Rge: 23-22S-33W
2623 feet from S Section Line, 1256 feet from E Section Line
Lease Name: FINNUP Well #: 2
County: FINNEY Total Vertical Depth: 2704 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1100		
CIBP		1790		WITH 2 SX CMT.
PROD	4.5	2704	0	WITH 425 SX CMT
SURF	8.625	340		WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/23/2018 9:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOSE REYES Company: AMERICAN WARRIOR Phone: (620) 275-2963

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/23/2018 1:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

(LEFT APPROXIMATELY 800' OF 2 3/8" TBG IN THE HOLE) CIBP @ 1790' WITH 2 SX CMT. CBL RAN ON 2/22/18 SHOWS TOC ABOVE 500' (RAN OUT OF FLUID). USABLE WATER IS COVERED. SET 2ND CIBP @ 1100' WHICH IS ABOVE THE CASING LEAK. TEST CASING TO 700#. HOLDING. PERFORATE 4 HOLES AT 360' & ATTEMPT TO PUMP INTO AT 700#. COULD NOT. CEMENT BEHIND THE 4 1/2" CASING IS ABOVE THIS POINT. RUN TBG TO 1071' & CIRCULATE CMT TO SURFACE WITH 65 SX CMT. TOOH WITH TBG & TOP OFF WITH 5 SX CMT. PUMP 35 SX CMT DOWN ANNULUS TO 200#.

Perfs:

Top	Bot	Thru	Comments
2586	2617		


INVOICED
APR 20 2018

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED
MAR - 6 2018
KCC DOUGGE CITY