

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-22508-00-00
Spot: NWNWSESW Sec/Twnshp/Rge: 11-20S-21W
1311 feet from S Section Line, 3845 feet from E Section Line
Lease Name: SHANK Well #: 1-11
County: NESS Total Vertical Depth: 4500 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4472	0	WITH 125 SX CMT
SURF	8.625	412		WITH 225 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/21/2018 3:30 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: SCOTT CORSAIR Company: AMERICAN WARRIOR Phone: (785) 398-2270

Proposed Plugging Method: RUN LOG ON TOP PART OF WELL. RUN TBG TO 4400' & SPOT 50 SX CMT & 200# HULLS. PULL TBG TO 1500' & SPOT 50 SX CMT & 200# HULLS. PRESSURE CASING. IF HOLD PERFORATE AT 415' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/22/2018 2:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

3/15/18: RAN BOND LOG & FOUND CMT FROM 1400' TO 450'. 3/21/18: RAN TBG TO 4400' & MIXED 50 SX CMT & 200# HULLS. PULLED TBG TO 1499' & MIXED 50 SX CMT & 200# HULLS. SDON. 3/22/18: RUN IN & TAGGED CMT AT 1281'. RAN TBG TO 1225' & MIXED 100 SX CMT & 400# HULLS. CMT DID NOT CIRCULATE. WAITED 1 HOUR & RAN IN. TAGGED CMT AT 950'. MIXED 200# HULLS THEN 30 SX CMT & 100# HULLS. DISPLACED CMT TO 450'. SHUT DOWN 1 HOUR. TAGGED CMT AT 750'. WAITED 1 HOUR & PRESSURED CASING TO 500#. PERFORATED AT 415'. RAN TBG TO 420' & MIXED CMT UNTIL IT CIRCULATED ON THE BACKSIDE OF THE TBG. SHUT IN BACKSIDE & MIXED UNTIL IT CAME UP BACKSIDE OF 4 1/2". USED 100 SX CMT. PULLED TBG & TOPPED OFF WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4395	4397		

INVOICED
APR 20 2018

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

Signed

Michael Maier
SA

(TECHNICIAN)

RECEIVED
MAR 27 2018
KCC DODGE CITY