

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-035-20479-00-00  
Spot: SENESW Sec/Twnshp/Rge: 17-31S-5E  
1751 feet from S Section Line, 2940 feet from E Section Line  
Lease Name: PENDERGRAFT Well #: 2  
County: COWLEY Total Vertical Depth: 2920 feet

Operator License No.: 33405  
Op Name: ANSTINE & MUSGROVE INC.  
Address: PO BOX 391  
PONCA CITY, OK 74602

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2920		125 SX
SURF	8.625	216		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/19/2018 8:00 AM  
Plug Co. License No.: 31539 Plug Co. Name: SAMS WELL SERVICE, INC.  
Proposal Rcvd. from: GARY ANSTINE Company: \_\_\_\_\_ Phone: (620) 441-8165

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 01/19/2018 5:00 PM KCC Agent: DUANE KRUEGER

**Actual Plugging Report:**

**Perfs:**

SET CIBP @ 2825', DUMP BAILED 2 SX CEMENT ON TOP OF PLUG. PERFORATED SQUEEZE HOLES @ 266'. RIH WITH TUBING @ 270', QES MIXED & PUMPED 125 SXS 60/40 POZMIX 4% GEL 2% CC & DISPLACED IN CASING. WELL ON VACUUM. WAITED 3 HOURS TAGGED CEMENT @ 450'. RIH WITH TUBING @ 270' QES MIXED & PUMPED 120 SXS 60/40 POZMIX 4% GEL 2% CC TO SURFACE. CEMENT CIRCULATED. LAYED TUBING DOWN TOPPED WELL BACK TO SURFACE. QES TICKET #54758.

Top	Bot	Thru	Comments
2859	2870	CSG	

INVOICED

Remarks: COMPLAINT

APR 20 2018

Plugged through: TBG

District: 02

Signed

Duane Krueger  
(TECHNICIAN)