

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-035-20294-00-00  
Spot: SESESW Sec/Twnshp/Rge: 17-31S-5E  
373 feet from S Section Line, 2882 feet from E Section Line  
Lease Name: PENDERGRAFT Well #: 1  
County: COWLEY Total Vertical Depth: 3370 feet

Operator License No.: 33405  
Op Name: ANSTINE & MUSGROVE INC.  
Address: PO BOX 391  
PONCA CITY, OK 74602

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2963		125 SX
SURF	8.625	251		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/23/2018 12:00 AM  
Plug Co. License No.: 31539 Plug Co. Name: SAMS WELL SERVICE, INC.  
Proposal Rcvd. from: GARY ANSTINE Company: \_\_\_\_\_ Phone: (620) 441-8165

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 01/23/2018 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

RIH WITH TUBING @ 2834', QES MIXED & PUMPED 40 SKS 60/40 POZMIX 4% GEL 3% CC W/ 100# HULLS & DISPLACED IN CASING. WAITED 2 HOURS, TAGGED CEMENT @ 2459'. PERFORATED SQUEEZE HOLES @ 300'-301' (4 HOLES). RIH W/TUBING @ 301', QES MIXED & PUMPED 125 SXS 60/40 POZMIX 4% GEL 2% CC (NO CIRCULATION) CEMENT ON VACUUM. WAITED 3 HOURS, TAGGED CEMENT @ 650'. RIH WITH TUBING @ 301' QES MIXED & PUMPED 130 SXS 60/40 POZMIX 4% GEL 2% CC TO SURFACE. CEMENT CIRCULATED. LAID TUBING DOWN. TOPPED WELL BACK TO SURFACE W/25 SXS.

Top	Bot	Thru	Comments
2877	2887	CSG	

INVOICED

Remarks: CEMENT TICKET 354880 - COMPLIANCE COMPLAINT

APR 20 2018

Plugged through: TBG

District: 02

Signed

Duane Krueger  
(TECHNICIAN)

JK