

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-035-19180-00-00  
Spot: NWNENE Sec/Twnshp/Rge: 15-33S-3E  
5027 feet from S Section Line, 744 feet from E Section Line  
Lease Name: MILLER Well #: 6  
County: COWLEY Total Vertical Depth: 3284 feet

Operator License No.: 33405  
Op Name: ANSTINE & MUSGROVE INC.  
Address: PO BOX 391  
PONCA CITY, OK 74602

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	3225		
PROD	5.5	3275		125 SX
SURF	8.625	100		150 SX

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/14/2018 8:00 AM  
Plug Co. License No.: 31539 Plug Co. Name: SAMS WELL SERVICE, INC.  
Proposal Rcvd. from: GARY ANSTINE Company: Phone: (620) 441-8165

Proposed Plugging Method: AS PER KCC RULES & REGS/ CIBP @ 3225' WITH 2 SX/ PERF 350' & CIRCULATE TO SURFACE.

Plugging Proposal Received By: JAY PFEIFER WitnessType: PARTIAL  
Date/Time Plugging Completed: 03/14/2018 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE, SET CIBP @ 3225', DROP BAILED 2 SXS CEMENT ON TOP OF PLUG. RIH ON WIRELINE, PERFORATED SQUEEZE HOLES 350'- 351', (4 HOLES). RIH WITH TUBING @ 352', QES ESTABLISHED CIRCULATION MIXED & PUMPED 90 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. LAYED DOWN TUBING, TOPPED WELL BACK TO SURFACE W/ 15 SXS. QES TICKET #55365.

Perfs:

Top	Bot	Thru	Comments
3275	3284		

Remarks: COMPLIANCE/DENIED TA

Plugged through: TBG

INVOICED

APR 20 2018

District: 02

Signed

DUANE KRUEGER  
(TECHNICIAN)