

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-20397-00-00
Spot: NENE Sec/Twnshp/Rge: 27-29S-8W
4620 feet from S Section Line, 660 feet from E Section Line
Lease Name: DUCKWORTH ALDEN Well #: 1
County: KINGMAN Total Vertical Depth: 4309 feet

Operator License No.: 30481
Op Name: APOLLO ENERGIES, INC.
Address: 10378 N 281 HWY
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4309	1644	0 SX
SURF	8.625	267		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/15/2017 8:00 AM
Plug Co. License No.: 30481 Plug Co. Name: APOLLO ENERGIES, INC.
Proposal Rcvd. from: JIM BYERS Company: _____ Phone: (620) 672-9001

Proposed Plugging Method: AS PER KCC RULE & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 11/15/2017 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

Perfs:

SANDED BACK TO 4130' CAPPED WITH 5 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 1644' PULLED CASING. TTIH 1273' SPOTTED 50 SX CEMENT TTOH. WAITED 2 HOURS TAGGED @ 870'. TTIH 790' SPOTTED 35 SX CEMENT. TTOH TO 320' CIRCULATED TO SURFACE WITH 120 SX CEMENT. WELL BLEW OUT AT 1150' WHEN PULLING CASING.

Top	Bot	Thru	Comments
4235	4245		

INVOICED


Remarks: COPLAND OUT OF GREAT BEND PROVIDED CEMENT. DENIED TA.

APR 2 '0 2018

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

1/8