

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-093-20753-00-02
 Spot: E2NW Sec/Twnshp/Rge: 15-22S-37W
3979 feet from S Section Line, 3254 feet from E Section Line
 Lease Name: PEARL Well #: #2-15
 County: KEARNY Total Vertical Depth: 3050 feet

Operator License No.: 30481
 Op Name: APOLLO ENERGIES, INC.
 Address: 10378 N 281 HWY
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2696		
CIBP		2805		
CIBP		3048		
PROD	5.5	3050	0	WITH 600 SX CMT
SURF	8.625	323		WITH 350 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/05/2018 8:00 AM
 Plug Co. License No.: 34612 Plug Co. Name: EXACT WELL SERVICE LLC
 Proposal Rcvd. from: GARY PISTER Company: EXACT WELL SERVICE Phone: (620) 672-1478

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 40 SX CMT & 150# HULLS. TEST CASING. IF HOLDS PUT 25 SX CMT AT 2100'. PULL TBG TO 1100' & SPOT 25 SX CMT. PULL TBG & PERFORATE AT 340. CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
 Date/Time Plugging Completed: 03/05/2018 2:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 40 SX CMT & 150# HULLS AT 2664'. PLUG AT 2106' WITH 25 SX CMT. LOAD HOLE. (CBL RAN 3/24/03 SHOWS TOC @ 820'. USABLE WATER COVERED). PLUG AT 1114' WITH 25 SX CMT. FULL CIRCULATION. PERFORATE 3 HOLES AT 350'. CIRCULATE CMT TO SURFACE WITH 100 SX CMT LEAVING THE 5 1/2" CASING & 5 1/2" X 8 5/8" ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
2979	2992		
2960	2973		
2918	2934		
2704	2710		
2676	2686	OH	

INVOICED


Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY COPELAND

APR 20 2018

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED
 MAR 20 2018
 KCC DODGE CITY

