

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-19447-00-00
Spot: NWSWNE Sec/Twnshp/Rge: 23-31S-5E
3630 feet from S Section Line, 2310 feet from E Section Line
Lease Name: SU-NEWMAN EVANS A Well #: 3
County: COWLEY Total Vertical Depth: 2322 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2.5	2320		75 SX
SURF	7	145		75 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/01/2018 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: R. A. (DICK) SCHREMMER Company: _____ Phone: (316) 524-1225

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 02/02/2018 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SWEDGED INTO 2 7/8" TUBING, ESTABLISHED RATE. COPELAND ACID MIXED & PUMPED 35 SXS CLASS A COMMON & DISPLACED IN CASING @ 1550'. WAITED OVERNITE & TAGGED CEMENT PLUG AT 1775'. LOADED HOLE & PRESSURED TUBING @ 150#. HELD OK. RIH IN WIRELINE, PERFORATED SQUEEZE HOLES 255-256' (4 HOLES). SWEDGED INTO TUBING, ESTABLISHED CIRCULATION. COPELAND ACID MIXED & PUMPED 118 SXS 60/40 POZMLX 2% GEL TO SURFACE. CEMENT CIRCUALTED. CEMENT TICKET #45026.

Perfs:

Top	Bot	Thru	Comments
2296	2302	CSG	

INVOICED

Remarks: DENIED TA

Plugged through: TBG

APR 2 0 2018

District: 02

Signed John K. Cook DISTRICT SUPERVISOR
(TECHNICIAN)