

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-19468-00-00
Spot: NESWSW Sec/Twnshp/Rge: 26-31S-5E
990 feet from S Section Line, 4290 feet from E Section Line
Lease Name: SU-PECK RICHARD Well #: 4
County: COWLEY Total Vertical Depth: 2297 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2290		100 SX
SURF	8.625	205		200 SX

Well Type: OIL UIC Docket No: Date/Time to Plug: 02/09/2018 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: R. A. (DICK) SCHREMMER Company: Phone: (316) 524-1225

Proposed
Plugging
Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 02/09/2018 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

RIH ON WIRELINE, SET CIBP @ 2240', DUMP BAILED 2 SXS CEMENT ON TOP OF PLUG. LOADED HOLE W/FLUID, PRESSURED CASING @ 200#, HELD OK. RIH ON WIRLINE, PERFORATED SQUEEZE HOLES 260'-261' (4 HOLES). SWEDGED INTO 4 1/2" CASING, COPELAND ACID SERVICE ESTABLISHED CIRCULATION, MIXED & PUMPED 125 SXS 60/40 POZMIX 4% GEL 2% CC TO SURFACE. CEMENT CIRCULATED. CEMENT TICKET #45039.

Top	Bot	Thru	Comments
2290	2297	OH	

Remarks: DENIED TA

Plugged through: TBG

INVOICED

APR 27 2018

District: 02

Signed

Duane Krueger
(TECHNICIAN)

SK