

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-19480-00-00
Spot: SESWSE Sec/Twnshp/Rge: 26-31S-5E
330 feet from S Section Line, 1650 feet from E Section Line
Lease Name: SU-STABECK Well #: 7
County: COWLEY Total Vertical Depth: 2308 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 4.5 | 2306 | | 100 SX |
| SURF | 8.625 | 208 | | 100 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/09/2018 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: R. A. (DICK) SCHREMMER Company: _____ Phone: (316) 524-1225

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 02/09/2018 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE, SET CIBP @ 2260'. DUMP BAILED 2 SXS CEMENT ON TOP OF PLUG. LOADED HOLE, PRESSURED CASING @ 250#, HELDOK. RIH ON WIRELINE, PERFORATED SQUEEZE HOLES 260' -261' (4 HOLES). SWEDGED INTO 4 1/2" CASING, COPELAND ACID SERVICE, ESTABLISHED CIRCULATION, MIXED & PUMPED 145 SXS 60/40 POZMIX 4% GEL 2% CC TO SURFACE. CEMENT CIRCUALTED. CEMENT TICKET #45040.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2295 | 2298 | CSG | |

INVOICED

Remarks: DENIED TA

APR 20 2018

Plugged through: TBG

District: 02

Signed

Duane Krueger
(TECHNICIAN)

VSK