

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-119-00101-00-01
Spot: SWSE Sec/Twnshp/Rge: 10-34S-27W
853 feet from S Section Line, 1713 feet from E Section Line
Lease Name: BOHLING Well #: 1-10
County: MEADE Total Vertical Depth: 6050 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5720		WITH 2 SX CMT
PROD	4.5	6050	2210	WITH 150 SX CMT
SURF	8.625	1379		WITH 900 SX CMT

Well Type: GAS UIC Docket No: Date/Time to Plug: 03/02/2018 1:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: CIBP @ 5940' WITH 2 SX CMT. PLUG AT 1420' WITH 12 SX GEL & 50 SX CMT. PLUG AT 440' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KEN SCOFIELD WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/02/2018 3:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

STACKED OUT AT 5720'. SET CIBP AT 5720' WITH 2 SX CMT PER KEN JEHLIK. 1ST PLUG AT 1420' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 449' WITH 50 SX CMT. 3RD PLUG AT 64' WITH 20 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5988	5994		
5968	5972		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

INVOICED

APR 2 0 2018

District: 01

Signed

[Signature]
(TECHNICIAN)

RECEIVED
MAR - 9 2018
KCC DODGE CITY

Form CP-2/3

KMS