

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-175-21572-00-00  
Spot: SENWNWSE Sec/Twnshp/Rge: 29-31S-34W  
2000 feet from S Section Line, 2258 feet from E Section Line  
Lease Name: SHAW C LEASE Well #: 1-29  
County: SEWARD Total Vertical Depth: 5842 feet

Operator License No.: 34318  
Op Name: BEREXCO LLC  
Address: 2020 N. BRAMBLEWOOD  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4870		WITH 2 SX CMT
CIBP		5000		
DVT		3260		WITH 325 SX CMT
PROD	4.5	5842	0	WITH 500 SX CMT
SURF	8.625	1465		WITH 475 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/07/2018 2:00 PM  
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING  
Proposal Revd. from: GREG KLAUS Company: BEREXCO Phone: (316) 772-8650

Proposed Plugging Method: SET CIBP @ 4870' WITH 2 SX CMT. PLUG AT 1740' WITH 30 SX CMT. RUN CBL FROM 600' TO 0'. IF CLEAR PERFORATE AT 550' & CIRCULATE CMT TO SURFACE. IF CMT IF TO 0' 2ND PLUG AT 550' WITH 40 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: PARTIAL  
Date/Time Plugging Completed: 03/07/2018 6:00 PM KCC Agent: HEITH WALSH

Actual Plugging Report:

SET CIBP @ 4870' WITH 2 SX CMT. PRESSURE TEST CASING TO 500# & HELD. PERFORATE AT 550'. PRESSURE TESTED CASING TO 500# & HELD. RTIH TO 1738'. 1ST PLUG AT 1738' WITH 30 SX CMT. TOOH WITH TBG TO 548'. 2ND PLUG CIRCULATE 45 SX CMT FROM 548' TO 0'. TOOH WITH TBG. TOP OFF 4 1/2" CASING WITH 5 SX CMT. PUMPED 30 SX CMT INTO THE 8 5/8" X 4 1/2" ANNULUS.

Perfs:

Top	Bot	Thru	Comments
5650	5657		
5314	5332		
4915	4924		

INVOICED

APR 20 2018

Remarks: USED 60/40 POZMIX 4% GEL BY GLOBAL CEMENTING.

Plugged through: TBG

District: 01

Signed

(TECHNICIAN)

RECEIVED  
MAR - 9 2018  
KCC DOUGIE CITY

Form CP-2/3