

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-175-21544-00-00
Spot: SWNWSESE Sec/Twnshp/Rge: 20-31S-34W
754 feet from S Section Line, 1110 feet from E Section Line
Lease Name: LAHEY G LEASE Well #: 1-20
County: SEWARD Total Vertical Depth: 5790 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1800		
CIBP		4810		WITH 2 SX CMT
CIBP		5550		
DVT		3253		WITH 325 SX CMT
PROD 4.5		5790	0	WITH 500 SX CMT
SURF 8.625		1467		WITH 250 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/07/2018 9:00 AM
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING
Proposal Rcvd. from: GREG KLAUS Company: BEREXCO Phone: (316) 772-8650

Proposed Plugging Method: SET CIBP @ 4810' WITH 2 SX CMT. SET CIBP @ 1800'. PRESSURE TEST CASING TO 300#. PLUG AT 1740' WITH 30 SX CMT. RUN CBL FROM 600' TO 0'. IF CLEAR PERFORATE AT 550' & CIRCULATE CMT TO SURFACE. IF NOT CLEAR RTIH TO 550' & CIRCULATE CMT TO SURFACE WITH TBG.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/07/2018 1:30 PM KCC Agent: HEITH WALSH

Actual Plugging Report:

SET CIBP @ 4810' WITH 2 SX CMT. SET CIBP 1800'. PRESSURE TEST CASING TO 300# & HELD. RAN CBL. CMT FROM 550' TO 0'. PERFORATE AT 550'. PRESSURE TESTED CASING TO 500# & HELD. RTIH TO 1738'. 1ST PLUG AT 1738' WITH 30 SX CMT. TOOH WITH TBG TO 548'. 2ND PLUG CIRCULATED 40 SX CMT FROM 548' TO 0'. TOOH WITH TBG. TOPPED OFF 4 1/2" CASING WITH 5 SX CMT. PUMPED INTO THE 8 5/8" X 4 1/2" ANNULUS. PRESSURED TO 500# RIGHT AWAY.

Perfs:

Top	Bot	Thru	Comments
5589	5604		
4856	4860		

INVOICED
APR 20 2018


Remarks: USED 60/40 POZMIX 4% GEL BY GLOBAL CEMENTING.

Plugged through: TBG

District: 01

RECEIVED
MAR - 9 2018
KCC DODGE CITY

Signed



(TECHNICIAN)

Kms