

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-175-21659-00-00
Spot: NESESWSW Sec/Twnshp/Rge: 20-31S-34W
639 feet from S Section Line, 4113 feet from E Section Line
Lease Name: LAHEY G Well #: 2-20
County: SEWARD Total Vertical Depth: 5847 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5530		WITH 2 SX CMT
DVT		3270		WITH 325 SX CMT
PROD	4.5	5847	0	WITH 175 SX CMT
SURF	8.625	1413		WITH 500 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/23/2018 11:00 AM
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING
Proposal Rcvd. from: GREG KLAUS Company: BEREXCO LLC Phone: (316) 772-8650

Proposed Plugging Method: CIBP @ 5530'. LAOD & TEST. PERFORATE AT 1450' WITH 50 SX CMT, 200# HULLS IN LAST 25 SX CMT. PERFORATE AT 550' WITH CMT TO 0'.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/23/2018 1:00 PM KCC Agent: HEITH WALSH

Actual Plugging Report:

CIBP @ 5530' WITH 2 SX CMT. PRESSURE TESTED 4 1/2" CASING TO 300# & IT HELD. PERFORATE AT 1450'. 1ST PLUG AT 1450' WITH 50 SX CMT WITH 200# HULLS IN LAST 25 SX CMT. PERFORATE AT 550'. 2ND PLUG CRICULATED 120 SX CMT FROM 550' TO 0'.

Perfs:

Top	Bot	Thru	Comments
5572	5578		

Remarks: USED 60/40 POZMIX 4% GEL BY GLOBAL CEMENTING.

Plugged through: CSG

INVOICED

APR 20 2018

District: 01

Signed _____

(TECHNICIAN)

RECEIVED
MAR - 5 2018
KCC DODGE CITY

Form CP-2/3