

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-175-21213-00-00
 Spot: SENESWNW Sec/Twnshp/Rge: 31-31S-32W
3304 feet from S Section Line, 4022 feet from E Section Line
 Lease Name: HATFIELD LEASE Well #: 1-31
 County: SEWARD Total Vertical Depth: 5889 feet

Operator License No.: 34318
 Op Name: BEREXCO LLC
 Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1800		WITH 2 SX CMT
CIBP		5500		
DVT		3234		WITH 250 SX CMT
PROD	4.5	5940	0	WITH 600 SX CMT
SURF	8.625	1705		WITH 675 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/23/2018 8:30 AM
 Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING
 Proposal Rcvd. from: GREG KLAUS Company: BEREXCO LLC Phone: (316) 772-8650

Proposed Plugging Method: SET CIBP @ 1800' WITH 2 SX CMT. PERFORATE AT 1740' WITH 50 SX CMT & 200# HULLS IN THE LAST 25 SX CMT. PERFORATE AT 550' WITH CMT TO 0'.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
 Date/Time Plugging Completed: 02/23/2018 10:30 AM KCC Agent: HEITH WALSH

Actual Plugging Report:

SET CIBP @ 1800' WITH 2 SX CMT. PRESSURE TESTED 4 1/2" CASING TO 500# & IT HELD. PERFORATE AT 1740'. 1ST PLUG AT 1740' WITH 50 SX CMT & 200# HULLS IN THE LAST 25 SX CMT. PERFORATE AT 550'. 2ND PLUG CIRCULATE 110 SX CMT FROM 550' TO 0'.

Perfs:

Top	Bot	Thru	Comments
5549	5556		

INVOICED

Remarks: USED 60/40 POZMIX 4% GEL BY GLOBAL CEMENTING.

APR 20 2018

Plugged through: CSG

District: 01

RECEIVED
 MAR - 5 2018
 KCC DODGE CITY



Signed _____
 (TECHNICIAN)

KMS
 Form CP-2/3