

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
111 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Barton County, Sec. 8 Twp 20S Rge. (E) 12(W)

Location as "NE/CNW%SW%" or footage from lines SW SW SE
Lease Owner Inger Oil Company
Lease Name Button Well No. 1
Office Address 1020 Central Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 11 19 59
Application for plugging filed _____ 19 _____
Application for plugging approved _____ 19 _____
Plugging commenced 11:30 PM September 11 19 59
Plugging completed 1:00 AM September 12 19 59
Reason for abandonment of well or producing formation _____

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3495 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	256'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud to 245', plug, 1/3 sack hulls, 20 sacks cement
Mud to 40', plug, 1/3 sack hulls, 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION

AUG 2 1962

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Garvey Drilling Company
Address RR 2 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
O. Brandenburg (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) [Signature]
(Address) _____

SUBSCRIBED AND SWORN TO before me this 1st day of August, 19 62

My commission expires April 14, 1963 Arthur J. Niles Notary Public.

WELL LOG

15.009.05234.0000

COMPANY **INGER OIL COMPANY**

SEC. 8 T. 20S R. 12W

FARM **BUTTON**

NO. **1**

LOC. **SW, SW, SE**


TOTAL DEPTH **3495'**

COUNTY **BARTON CO., KANSAS**

COMM. **September 4, 1959**

COMP. **September 12, 1959**

CONTRACTOR **GARVEY DRILLING COMPANY**



CASING **8 5/8" @ 254' W/175 sax.**

ELEVATION

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

146	Surface soil & sand
151	Hard sand
180	Sand
238	Sand & clay
254	Blue shale
270	Shale & shells
709	Red bed
719	Anhydrite
1250	Shale & shells
1510	Shale
1885	Lime
1900	Shale
2140	Lime & shale
2360	Shale & lime
2470	Shale
2545	Lime
2770	Shale & lime
2930	Lime & shale
3425	Lime
3556	Lime & shale
3495	Lime
3495	T. D.

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 2 1959
 CONSERVATION DIVISION
 Wichita, Kansas

State of KANSAS

County of BARTON

ss:

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 BUTTON well.

Verne A. Morris

Subscribed and sworn to before me this 2nd day of October 19 59

My Commission Expires: November 12, 1962

[Signature]
NOTARY PUBLIC