


WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Barton County, Sec. 8 Twp. 20S Rge. 12W (E) (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SE NE
Lease Owner HEXAGON OIL COMPANY & FRANCO-CENTRAL OIL CO.
Lease Name LANTERMAN Well No. 1
Office Address 705 Fourth National Bank Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 7, 19 51
Application for plugging filed May 7, 19 51
Application for plugging approved May 7, 19 51
Plugging commenced May 7, 19 51
Plugging completed May 7, 19 51
Reason for abandonment of well or producing formation D & A
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Hollis
Producing formation Depth to top Bottom Total Depth of Well 3455 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	221'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from 3455' to 215'. Set bridge and dumped 15 sacks cement filled with mud to 40' and cement to surface with 10 sacks cement to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION
MAY 16 1951
CONSERVATION DIVISION
Wichita, Kansas

5-16-51

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Hexagon Oil Company
Address 705 Fourth National Bank Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. W. Sebitts (employee of owner) or (owner) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature)
705 Fourth National Bank Building, Wichita 2, Kan.
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of May, 19 51

My commission expires January 28, 1953

Notary Public.

PLUGGING
FILE SEC. 8 T. 20 R. 12W
BOOK PAGE 80 LINE 9

COMPANY:

HEXAGON OIL COMPANY &
FRANCO-CENTRAL OIL COMPANYRotary Drilling Commenced: 4-27-51
Rotary Drilling Completed: 5-7-51

LOCATION:

LANTERMAN #1, SE 3/4 1/2
Sec. 8-203-12W, Barton County, Kansas

CONTRACTOR

PICKRELL DRILLING COMPANY, INC.
Wichita, Kansas

CASING RECORD:

221' (7 Jts.) 8 5/8" Row Casing 24 1/2 J-55 Smis. set at 221' in a 12 1/2" hole, Cemented with 160 sacks of cement. Circulated cement.

LOG

(Figures indicate bottom formation - measurements from top rotary bushings.)

Cellar	5	Circulate for samples at 3235'
Surface Sand	70	" " " " 3265'
Sand	140	" " " " 3275'
Iron	150	" " " " 3310'
Shale & Shells	290	" " " " 3347'
Red Bed	585	" " " " 3410'
Shale & Salt	1460	" " " " 3417'
Shale & Lime	2170	" " " " 3426'
Shale Break	2330	" " " " 3430'
Shale & Lime	2635	" " " " 3457'
Shale	2350	" " " " 3450'
Lime	3148	" " " " 3455'
Lime & Shale	3184	
Lime	3423	Slope Test at 1,000' - 0° off.
Arbuckle	3428	" " " 1,500' - 0° "
Lime Arbuckle	3437	" " " 2,000' - 0° "
Lime	3455 Rotary T. D.	" " " 2,500' - 0° "
		" " " 3,000' - 0° "

S. L. H. at 2,500' - OK.
" " " " 3,000' - OK.**RECEIVED**
STATE CORPORATION COMMISSION

The undersigned, C. W. Sobits, Secretary of PICKRELL DRILLING COMPANY, INC., hereby certifies in behalf of said corporation, that the above log is a true and correct log of the formation encountered in drilling the above CONSERVATION DIVISION as reflected by the Daily Drilling Reports.

MAY 16 1951
Wichita, Kansas

PICKRELL DRILLING COMPANY, INC.

By

Secretary

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS

BE IT REMEMBERED that on this 10th day of May, 1951, before me, the undersigned, a Notary Public, duly commissioned, in and for the county and state aforesaid, came C. W. Sobits, Secretary of Pickrell Drilling Company, Inc., a corporation of the State of Kansas, personally known to me to be such officer, and to be the same person who executed as such officer the foregoing instrument of writing in behalf of said corporation, and he duly acknowledged the execution of the same for himself and for said corporation.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal on the day and year last above written.

Ethel Zimmerman
Notary Public

My commission expires January 28, 1953.

