

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-009-24,414.0000

LEASE NAME Moses

WELL NUMBER 1

330 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 13 TWP. 20 RGE. 14 (S) or (W)

COUNTY Barton

Date Well Completed 04-01-90

Plugging Commenced 04-01-90

Plugging Completed 04-01-90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Globe Exploration, Inc.

ADDRESS P.O. Box 12 Great Bend, KS 67530

PHONE# (316) 792-7607 OPERATORS LICENSE NO. 6170

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-30-90 (date)

by Herb Doines (KCC District Agent's Name).

Is ACO-1 filed? to be filed If not, Is well log attached? yes
by operator

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3610

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Bottom Plug: @ 3495' w/25 sacks cement thru drill pipe
Next Plug: @ 800' w/25 " " " " " 15 sacks in Rat Hole
Next Plug: @ 560' w/100 " " " " " fill up water well
Top Plug: @ 40' w/10 " " " " "

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address P.O. Box 823 Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Globe Exploration, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Leonard Williamson

(Employee of Operator) or (XXXXXXXXXX) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Leonard Williamson

(Address) P.O. Box 823 Great Bend, KS 67530

STATE CORPORATION COMMISSION
4-6-90
DOROTHY M. HAGUE
NOTARY PUBLIC
STATE OF KANSAS
My Appl. Exp. 5-5-90
RESERVATION DIVISION
Wichita, Kansas
APR 06 1990
SUBSCRIBED AND SWORN TO before me this 3rd day of April, 19 90
Dorothy M Hague
Notary Public

My Commission Expires: 5-5-90

DRILLER'S WELL LOG

Date Commenced; March 26, 1990
Date Completed; April 1, 1990

Globe Exploration, Inc.
MOSES #1
S/2 S/2 SE
Sec. 13, T20S, R14W
Barton County, Ks.

ELEVATION: 1891 K.B.

- 0 - 317' Surface Soil, Sand, Shale
- 317 - 779' Red Bed
- 779 - 802' Anhydrite
- 802 - 1600' Shale
- 1600 - 2480' Lime & Shale
- 2480 - 2998' Lime
- 2998 - 3150' Shale & Lime
- 3150 - 3163' Lime
- 3163 - 3239' Shale
- 3239 - 3250' Lime & Shale
- 3250 - 3474' Lime
- 3474 - 3505' Shale, Lime, Chert, Sand
- 3505 - 3610' Dolomite
- 3610' RTD

Surface Pipe: Set used 8-5/8",
25# pipe @509' w/300 sacks
60/40 pozmix 2% gel 3% cc.

A F F I D A V I T


STATE OF KANSAS
COUNTY OF BARTON) ss

Leonard Williamson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 3rd day of April 1990.

Dorothy M. Hague
Notary Public



APR 06 1990
CONSERVATION DIVISION
Wichita, Kansas