


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Barton County. Sec. 13 Twp. 20S Rge. 14 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines NW NW SE  
Lease Owner Frontier Oil Company  
Lease Name No. 1 Moses Well No. 1  
Office Address 580 Fourth National Bank Bldg. - Wichita  
Character of Well (completed as Oil, Gas or Dry Hole) D & A  
Date well completed July 3 19 59  
Application for plugging filed July 3 19 59  
Application for plugging approved July 3 19 59  
Plugging commenced July 3 19 59  
Plugging completed July 3 19 59  
Reason for abandonment of well or producing formation D & A



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Harold J. Hollis  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3606 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	795'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Broke down drill pipe. Filled hole with heavy mud. Set plug @ 785, cemented with 25 sacks 1/2 sack hulls. Set middle plug @ 300' with 25 sacks cement, 1/2 hulls. Set top plug @ 40', 10 sacks cement, 1/2 hulls.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 8 1959  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Red Tiger Drilling Co.  
Address Box 173, Russell, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
George A. Angle (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George A. Angle  
580 4th Nat'l Bank Bldg. - Wichita, Ks.  
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of July, 19 59

Maxine Head  
Notary Public.

My commission expires 11-17-62

PLUGGING  
FILE SEC. 13 T. 20 R. 14 W.  
BOOK PAGE 42 LINE 32

DRILLERS LOG

No. 1 Moses

CASING RECORD: 8 5/8" @ 795' w/250 sx cement  
 COMPANY: Frontier Oil Company  
 CONTRACTOR: Red Tiger Drilling Co.  
 COMMENCED: June 28, 1959  
 COMPLETED: July 3, 1959  
 DESCRIPTION: NW NW SE 13-20S-14W Barton County Kansas  
 ELEVATION: 1883 DF 1886 RB  
 TOTAL DEPTH: 3606' (-1720)

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sod Sand	0	40	
Sand	40	180	
Sand Streak and Shale	180	787	
Anhydrite	787	815	
Shale and Shells	815	1170	
Shale Shells	1170	1600	
Shale and Lime	1600	1680	
Shale Lime	1680	1880	
Shale and Lime	1880	1990	
Lime and Shale	1990	2160	
Shale and Lime	2160	2430	
Shale Lime Streaks	2430	2675	
Shale and Lime	2675	2870	
Lime and Shale	2870	3000	
Lime Shale	3000	3085	
Lime and Shale	3085	3165	
Shale and Lime	3165	3265	
Lime	3265	3600	
Arbuckle Lime	3600	3606	

RECEIVED  
 STATE CORPORATION COMMISSION

JUL 8 1959  
 CONSERVATION DIVISION  
 Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

FRONTIER OIL COMPANY

*George A. Angle*  
 George A. Angle

Subscribed and sworn to before me this 7th day of July, 1959.

*Mapone Head*  
 Notary Public

My Commission Expires:

11-17-62

PLUGGING  
 FILE SEC. 13 T. 20 R. 14W  
 BOOK PAGE 49 LINE 32