


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Barton County. Sec. 13 Twp. 20S Rge. 14W (X) (W)  
Location as "NE/CNW/SW" or footage from lines SE 1/4 NW 1/4 NE 1/4  
Lease Owner Leben Drilling, Inc. & R. S. C. Oil Co.  
Lease Name Stolz Well No. 2  
Office Address 905 Central Bldg., Wichita, Kansas.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 2-4-59 19  
Application for plugging filed 2-4-59 19  
Application for plugging approved 2-4-59 19  
Plugging commenced 2-4-59 19  
Plugging completed 2-4-59 19  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production -- 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Donald Truan  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3555' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	800'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mud to 350', set plug with 1/4 sack hulls & 25 sacks cement,  
Mud to 40' with 1/2 sack hulls & 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 24 1959  
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Leben Drilling, Inc.  
Address 905 Central Bldg., Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick ss.  
I, Frank Hamlin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Frank Hamlin  
905 Central Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 20th day of February, 1959

My commission expires June 17, 1961  
Ruth N. Benjamin Notary Public.

PLUGGING  
FILE SEC. 13 T. 20 R. 14W  
BOOK PAGE 16 LINE 41

DRILLER'S LOG

RECEIVED  
 STATE GEOLOGICAL COMMISSION  
 MAR 24 1959  
 CONSERVATION DIVISION  
 Wichita, Kansas

COMPANY: LEBEN DRILLING, INC.  
 CONTRACTOR: LEBEN DRILLING, INC.  
 FARM: STOLZ #2  
 LOCATION: SE $\frac{1}{4}$  NW $\frac{1}{4}$  NE $\frac{1}{4}$  SEC. 13-20S-14W,  
 BARTON COUNTY, KANSAS  
 COMMENCED: JANUARY 26, 1959  
 COMPLETED: FEBRUARY 4, 1959

0	10	Surface Clay
10	255	Sand, Shale & Shells
255	360	Sand
360	788	Redbed
788	870	Anhydrite
870	1590	Shale & Shells
1590	2495	Lime & Shale
2495	3370	Lime & Shale
3370	3555	Lime
	<u>3555</u>	<u>Rotary Total Depth - D &amp; A</u>

TOPS:

Anhydrite	788
Heebner	3136
Toronto	3152
Douglas	3164
Brown Lime	3237
Lansing K.C.	3247
Base K.C.	3471
Conglomerate	3485
Arbuckle	None
Rotary T.D.	3555

Set 8 5/8" surface casing @ 800' with 225 sacks common cement, 2% CaCl. and 225 sacks Sunset cement.

I, Frank Hamlin, do hereby certify that the above and foregoing is a true and correct copy of the log of the Stolz #2, located SE $\frac{1}{4}$  NW $\frac{1}{4}$  SE $\frac{1}{4}$  of Section 13, Township 20 South, Range 14 West, Barton County, Kansas, as reflected by the files of Leben Drilling, Inc.

LEBEN DRILLING, INC.

By: Frank Hamlin  
 Frank Hamlin

STATE OF KANSAS )  
 COUNTY OF SEDGWICK ) ss:

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 20th day of February, 1959.

Ruth N. Benjamin  
 Ruth N. Benjamin, Notary Public

My Commission Expires:  
 June 17, 1961

PLUGGING  
 FILE: SEC 13 T 20 R 14W  
 BOOK: PAGE 16 LINE 41