

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Barton

County. Sec. 13 Twp. 20 Rge. 14 (E) W (W)

Location as "NE/CNW/SE" or footage from lines NE/4 NE/4 SE/4

Lease Owner FRONTIER OIL COMPANY

Lease Name Frontier Oil Co- Moses Well No. 2

Office Address 580 Fourth National Bldg., Wichita, Kansas.

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced Dec 16 19 60

Plugging completed Dec 27 19 60

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES.



Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation Depth to top Bottom Total Depth of Well 3544 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3544 feet to surface feet for each plug set.

Well had been plugged back from 3544 to 3524; Hole filled with sand from 3524 to 3370 (Preforation at 3379) Five sacks of cement placed in bottom of hole with dump bailer. Pipe shot off at 2841 ft. and pulled from well; and hole filled with mud to 320 feet; Twenty foot rock bridge installed between 320 feet and 300 feet; 100 sacks of cement poured in hole, forming cement plug to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION
JAN 10 1961 1-10-61
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnes and Sons Pipe Pulling Co.,
Address Russell, Kansas.

STATE OF KANSAS COUNTY OF SEDGWICK ss.
George A. Angle (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George A. Angle
580 Fourth Natl. Bank Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of January, 1961

Notary Public.

My commission expires 11-17-62.

DRILLERS LOG

No. 2 Moses

CASING RECORD: COMPANY: Frontier Oil Company DESCRIPTION: NE NE SE
 8 5/8" @ 794 CONTRACTOR: Red Tiger Drilling Co. 13-208-14W
 w/450 ex cement Barton County
 Kansas
 8 1/2" @ 3543 COMMENCED: July 17, 1959 ELEVATION: 1888 DF
 w/100 ex COMPLETED: July 29, 1959 1891 RB
 TOTAL DEPTH: 3544'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand	0	180	
Shale and Sand	180	435	
Shale sand Red Bod	435	784	
Anhydrite	784	825	
Shale	825	890	
Shale Shells	890	1600	
Shale and Lime	1600	1640	
Shale Shells	1640	2000	
Lime and Shale	2000	2245	
Shale Shells	2245	2405	
Shale and Lime	2405	2885	
Lime Shale	2885	2970	
Lime and Shale	2970	3180	
Lime Shale	3180	3232	
Lime	3232	3510	
Lime Chert	3510	3533	
Lime	3533	3544	

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 20 1961
 CONSERVATION DIVISION
 Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

FRONTIER OIL COMPANY

George A. Angle
 George A. Angle

Subscribed and sworn to before me this 30th day of July, 1959.

Maryne Head
 Notary Public

My Commission Expires:

11-17-62